SECTION 10538

METAL CANOPIES

PART 1 GENERAL

1.01 SUMMARY

- A. Related Sections:
 - 1. 02201 Earthwork for Buildings.
 - 2. 03300 Cast-In-Place Concrete.

1.02 SUBMITTALS

- A. Submit properly identified product and technical data before starting work.
 - 1. Shop Drawings: Submit shop drawings for review, showing not less than the following:
 - a. Fabrication details.
 - b. Roof water drainage details.
 - c. Erection details.
 - d. Anchorage details.
 - e. Flashing details.
- B. Engineering Design Computations:
 - 1. Submit for record purposes, signed and sealed computations prepared by an engineer licensed in the State of Florida showing conformance to the applicable requirements of the:
 - a. Standard Building Code.
 - b. Florida Department of Education, Office of Educational Facilities - State Requirements for Educational Facilities - 1997 (SREF).

PART 2 PRODUCTS

- 2.01 MANUFACTURERS
 - A. Metal Canopy:

- 1. Hurr-I-Cane Awning Shutter Company, Hialeah, FL: "Span-Aire" Aluminum, Pre-Fabricated Canopy Roof System.
- 2. Dittmer Architectural Aluminum, Winter Springs, FL: Ditt-Deck aluminum canopy.
- Alcan Building Products, Division of Alcan Aluminum Corporation, Warren, OH: Alcan Aluminum Canopies.

2.02 FABRICATION

A. Component Finish: Conform to Aluminum Association Specification AA-M-10C-22A-21, clear anodize.

PART 3 EXECUTION

3.01 INSPECTION

A. Do not proceed with the work of this section until conditions detrimental to the proper and timely completion of the work have been corrected in an acceptable manner.

3.02 INSTALLATION

- A. Install aluminum canopy roof system plumb, true, and level according to manufacture's recommendations and accepted shop drawings.
 - The Contractor shall install all prefabricated parts or assembly systems using tamper proof fasteners.
 - 2. Repair or replace damaged components at no cost to the Board.

END OF SECTION